



GENERAL NOTES:

1. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION AND ELEVATION OF ALL UTILITIES BEFORE ANY EXCAVATION BEGINS. THE CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR ANY DAMAGE TO UTILITIES.
2. THE CONTRACTOR SHALL CONTACT ALL LOCAL UTILITIES AND TEXAS ONE CALL SYSTEM BEFORE COMMENCING ANY EXCAVATION OR DIGGING OPERATIONS.
3. BRACE UTILITY POLES AS REQUIRED TO MAINTAIN STABILITY OF THE POLES DURING CONSTRUCTION.
4. NO MANHOLES SHALL BE RAISED MORE THAN 1'-0" THROUGH THE USE OF GRADE RINGS.
5. NO PLASTIC OR BRICK MANHOLES SHALL BE BUILT.
6. FIBERGLASS MANHOLES ACCEPTABLE ONLY WHERE SHOWN ON PLANS AND AS DETAILED BY SEPARATE DRAWING.
7. ALL MATERIALS SHALL BE DOMESTIC / USA.
8. WHEN CROSSING ROADWAYS, CRUSHED LIMESTONE BASE MATERIAL SHALL BE TxDOT ITEM 248, TYPE A, GRADE 2 AND SHALL BE COMPACTED TO A MINIMUM OF 95% A.S.T.M. D1557, METHOD D @ + OR - 2% OPTIMAL MOISTURE AND LIFTS NOT TO EXCEED 6 INCHES.
9. ALL INFRASTRUCTURE SHALL MEET MINIMUM CURRENT EFFECTIVE TCEO STANDARDS.

Harker Heights

DEPARTMENT OF PUBLIC WORKS

SANITARY SEWER DETAILS

ENGINEER: _____

SCALE: N.T.S.

DATE: 3/14/11

DRAWN BY: _____

SHEET # _____

CHECKED BY: _____

TEXAS ONE CALL SYSTEM
1-800-245-4545
STOP CALL BEFORE YOU DIG